

NW Ohio Area Computer Services Coop

Ref. No.	ODOT	Item Description	Quantity	Unit	Total Unit Cost	Subtotal
	CMS					
Parking Lot						
1	201	CLEARING AND GRUBBING	1	LS		\$ -
2	202	GUARD POST REMOVED	4	EA.		\$ -
3		PRECAST PARKING BLOCK	10	EA.		\$ -
4	203	STONE EXCAVATION	810	CY		\$ -
5	203	EXCAVATION	30	CY		\$ -
6	204	MIRAFI 500X GEOMESH	2,424	SY		\$ -
7	304	8" 304 AGGREGATE BASE	540	CY		\$ -
8	407	TACK COAT AT 0.05 GAL/SY	121	GAL		\$ -
9	301	3 1/2" ASPHALT BASE	237	CY		\$ -
10	448	1 1/2" 448 ASPHALT , TYPE I, PG 64-22	102	CY		\$ -
11	452	6" CONCRETE PAD FOR DUMPSTER	80	SF		\$ -
12	642	PAVEMENT MARKINGS (PARKING STALL LINE)	1,045	LF		\$ -
13	642	PAVEMENT MARKINGS (HANDICAP WHEEL CHAIR SYMBOL)	2	EA		\$ -
14	642	PAVEMENT MARKINGS 8" WIDE (TRANSVERSE/DIAGONAL LINE, TYPE 1))	157	LF		\$ -
Roadway Sub-Total						\$ -

Ref. No.	ODOT	Item Description	Quantity	Unit	Total Unit Cost	Subtotal
	CMS					
Storm Sewer						
15	811	2-2B CATCH BASIN REMOVED AND RELOCATED	1	EA		\$ -
16	811	6" STORM CONDUIT TYPE "B" W/ GRANULAR BACKFILL	105	FT		\$ -
17	811	6"*6" *6" WYE	1	EA		\$ -
18	811	2-2B CATCH BASIN	1	EA		\$ -
Storm Sewer Sub-Total						\$ -

Ref. No.	ODOT	Item Description	Quantity	Unit	Total Unit Cost	Subtotal	
	CMS						
Incidentals							
19	Special	AS-BUILT CONSTRUCTION PLANS	1	LS		\$ -	
20	624	MOBILIZATION	1	LS		\$ -	
21	614	MAINTAINING TRAFFIC/PHASING OF WORK	1	LS		\$ -	
22		Grading, Seeding and Restoration	1	LS		\$ -	
23	Special	COMPACTION TESTING ALLOWANCE	1	LS	\$ 1,000.00	\$ 1,000.00	
24	Special	ASPHALT TESTING ALLOWANCE	1	LS	\$ 1,000.00	\$ 1,000.00	
					Incidentals Sub-Total		

Ref. No.	ODOT	Item Description	Quantity	Unit	Total Unit Cost	Subtotal	
	CMS						
Alternative Work							
25	202	WALK/CURB COMBO REMOVED (INCD/SAW CUT)	100	SF		\$ -	
26	202	EXISTING CONCRETE APRRONS REMOVED (INCD/SAW CUT)	180	SF		\$ -	
27	608	WALK/CURB COMBO INSTALLED	100	SF		\$ -	
28	451	6" REINFORCED CONCRETE PARKING LOT	180	SF		\$ -	
						\$ -	
					Sub-Total		\$ -

Project Bid Total (Asphalt Option)					\$ -
---	--	--	--	--	-------------