

NW Ohio Area Computer Services Coop

Ref. No.	ODOT	Item Description	Quantity	Unit	Total Unit Cost	Subtotal
	CMS					
Parking Lot						
1	201	CLEARING AND GRUBBING	1	LS		\$ -
2	202	GUARD POST REMOVED	4	EA.		\$ -
3		PRECAST PARKING BLOCK	10	EA.		\$ -
4	203	STONE EXCAVATION	432	CY		\$ -
5	203	EXCAVATION	30	CY		\$ -
6	451	6" REINFORCED CONCRETE PARKING LOT	21,814	SF		\$ -
7	642	PAVEMENT MARKINGS (PARKING STALL LINE)	1,045	LF		\$ -
8	642	PAVEMENT MARKINGS (HANDICAP WHEEL CHAIR SYMBOL)	2	EA		\$ -
9	642	PAVEMENT MARKINGS 8" WIDE (TRANSVERSE/DIAGONAL LINE, TYPE 1))	157	LF		\$ -
Roadway Sub-Total						\$ -

Ref. No.	ODOT	Item Description	Quantity	Unit	Total Unit Cost	Subtotal
	CMS					
Storm Sewer						
10	811	2-2B CATCH BASIN REMOVED AND RELOCATED	1	EA		\$ -
11	811	6" STORM CONDUIT TYPE "B" W/ GRANULAR BACKFILL	105	FT		\$ -
12	811	6"*6" *6" WYE	1	EA		\$ -
13	811	2-2B CATCH BASIN	1	EA		\$ -
Storm Sewer Sub-Total						\$ -

Ref. No.	ODOT	Item Description	Quantity	Unit	Total Unit Cost	Subtotal
	CMS					
Incidentals						
14	Special	AS-BUILT CONSTRUCTION PLANS	1	LS		\$ -
15	624	MOBILIZATION	1	LS		\$ -
16	614	MAINTAINING TRAFFIC/PHASING OF WORK	1	LS		\$ -

17		Grading, Seeding and Restoration	1	LS		\$ -
18	Special	COMPACTION TESTING ALLOWANCE	1	LS	\$ 1,000.00	\$ 1,000.00
19	Special	CONCRETE TESTING ALLOWANCE	1	LS	\$ 1,000.00	\$ 1,000.00
Incidentals Sub-Total						

Ref. No.	ODOT	Item Description	Quantity	Unit	Total Unit Cost	Subtotal
	CMS					
Alternative Work						
20	202	WALK/CURB COMBO REMOVED (INCD/SAW CUT)	100	SF		\$ -
21	202	EXISTING CONCRETE APPRONS REMOVED (INCD/SAW CUT)	180	SF		\$ -
22	608	WALK/CURB COMBO INSTALLED	100	SF		\$ -
23	451	6" REINFORCED CONCRETE PARKING LOT	180	SF		\$ -
						\$ -
Sub-Total						\$ -

Project Bid Total (Concrete Option)					\$ -
--	--	--	--	--	-------------